

Before We Start.

Our goal is to install the most durable and well-designed floors for you and/or your client. We don't need a lot to make that happen, but there are a few items that are integral to our success. Jacob or Nick M. will be working with you in order to ensure these items are on site and ready to rock before the team arrives. Information regarding pricing or change orders for your project can be provided by your DCD Project Manager.



POWER

Single Phase 240V – 30/50 amp or Three Phase 240V – 50/60 amp or Three Phase 480V
Whip provided by DCD 3-phase breaker by client, 3-5 Dedicated 110v Outlets



WATER

Water is utilized at various stages throughout our process. Access to a water supply near the working area helps maintain efficiency and effectiveness.



LIGHTS

A well-lit space allows our craftsman to see the floor as they install your system. This gives them the opportunity to enjoy the beauty or identify problem areas and fix them prior to completion.



HVAC

Air circulation in a closed-in space allows a new slab to acclimate in the intended environment. By getting in after the slab has had time to acclimate, we can patch any cracks that appear during the cure. Products utilized for our systems have temperature and humidity thresholds that are much easier to meet in a controlled space.



TRASH

While our processes can provide “green” flooring solutions, we do produce some waste. Our team will need access to a dumpster while on-site.



FACILITIES

In a world of automation, we take pride in the human element that we have to offer. This means that we sometimes have to #1 or #2. Having operational facilities on site can help us mitigate complaints from the neighbors.



PATCHING

Even the newest of floors sometimes require patching and repairs in order to create the best finish possible. Unless noted on your proposal, patching and repairs will be discussed as they present themselves. Pricing depends on several variables and your project manager will chat with you about the options.



EMPTY SPACE

We lose a lot of friends on this one, but that's the life we're willing to live in order to provide a stellar floor. We ask for:

- Exclusive access to the floor during our process
- All doors and trim to be removed or not yet installed
- Any non-permanent items removed off the floor
- An initial sweep & scrape to remove large debris and excessive dirt